

Project information

New construction: Schlierbach house for children and education

Due to its location, the new house for children and education combines the Dr.-Irmgard-Frank Kindergarten and the school from both a spatial and functional perspective. The basement accommodates a canteen for students and Kindergarten pupils. A media library and a project and learning room provide a welcoming atmosphere. The ground floor is intended for preschool children and incorporates a spacious sports room, a dorm room for Kindergarten pupils staying for full-day care and staff rooms, as well as three group rooms for children attending preschool. A joint kitchen completes this area.

Bohle Innenausbau GmbH & Co. KG, Stuttgart carried out interior work for three group rooms for 30 children each aged 0 to 3, as well as a canteen at the adjacent elementary and secondary school, including project rooms and a media library.

The basement was constructed with concrete slabs while the ground floor is of wood construction.

Start of construction: November 2011
Scheduled completion date: August 2012
Order volume: approx. 200,000 Euros

Scope of supply:

- Rigidur plates were installed on timber walls with a substructure made from spring rails – approx. 450 m².
- The suspended ceilings were designed using perforated drywall ceilings – approx. 780 m².
- F-30 timber glass elements were supplied and installed – 18 OFF

